

**ADDENDUM - II for “Establishment of 400 KLD Capacity Common Effluent Treatment Plant with 5 Years of Operation and Maintenance at Mega Food Park, at Buggapadu (V), Sathupally (M), Khammam District on “Design, Engineering, Construction, Supply, Installation, Testing, Erection & Commissioning basis”.**

<b>S.NO</b>	<b>PAGE NO</b>	<b>SECTION/CLAUSE NO</b>	<b>SPECIFICATION REQUIREMENTS</b>	<b>PRE-BID QUERIES</b>	<b>TSIIC REPLY</b>
1	11	2.1.b Scope of Project	Construction includes all civil works	Request you to furnish us the soil geo technical data for civil design.	Geo Technical (Soil) Investigation are to be done by the Bidder. The bidder shall factor the cost of this activity and submit the Financial bid. As per earlier Soil investigation reports, bidder can consider of 20T/sqm at 1 mt depth. However, bidder needs to verify and confirm the same at the specific site before execution.
2	11	2.1 f. Scope of Project	Collection tanks to be designed for storage of capacity 1 day.	Please confirm the bidder has to consider 2nos. untreated collection tank capacity each of capacity 400 m3 and 2 nos.Treated tank collection tank each of capacity 400 m3.	Collection tanks for the Untreated water will be same (i.e. 2 Nos.) as given in RFP document whereas for Treated water only 1 No. with 400 KLD capacity should be considered.
3	13	2.2 Special conditions	Sludge is to be handled and disposed propoerly	Kindly confirm the distance between the project site and sludge disposal site.	CETP sludge shall be stored on site as per the guidelines of MoEF&CC/TSPCB and then sent to the nearest designated secured land filing site i.e. TSDF Dundigal, Hyderabad.
4				Please confirm the right of way of sludge disposal site is excluded from the scope of bidder	There is no sludge disposal site in the Food Park. The sludge shall be temporarily stored at the CETP site as per norms and then disposed at TSDF Dundigal.
5				Please confirm the same sludge disposal site can be used for other solid waste disposal	Does not arise
6		General		Please confirm the supply of water for construction during erection & commissioning and during O&M is excluded from the scope of bidder	Bidder has to make his own arrangements to draw water from the water supply system of Food Park by paying necessary charges.

7		General		Please confirm the supply of Electricity for construction during erection & commissioning and for operation of CETP is excluded from the scope of bidder	Bidder has to make his own arrangements in regard to power supply during construction and erection from NPDCL by paying necessary charges.
8	8	1.1.1 Description of work	400 KLD CETP IN Modular Basis	Please clarify the term 'modular basis'.	The facility is dependent on seasonal product and the effluent inflow would vary there by necessitating modular approach.
9	11	2.1.b Scope of Project	Construction includes all civil works	Please confirm the invert level of untreated waste water collection tank.	Please refer to Pg. No 38 in the RFP for the invert levels.
10	3.2.2		DG Set Sizing Calculation	Please confirm whether all the blowers to be operated during power shut down.	It is Bidder's scope to ensure required power backup from DG available during the power shutdown.
11	3.2.2			Please confirm the supply of diesel is excluded from the scope of bidder.	Supply of diesel is in scope of bidder.
12	3.2.2			Please confirm the frequency and duration of expected EB power shut down	Currently there is no power shutdown. The bidder has to make suitable arrangements for unexpected power shut down.
13				For furnishing EMD, we request you to accept BG instead of Demand Draft.	Bank Gurantee is also accepted.

**Sd/-**  
**CHIEF ENGINEER**